

Area 2 — excavation to 1120.9
square no. / depth / volume
Total cut = 1,529.8 m³ Total fill = 0.0 m³

		1 +1.51 m 2.2 m³	2 +1.98 m 4.4 m³	3 +2.44 m 2.8 m³	4 +4.11 m 0.7 m³
		5 +1.67 m 8.5 m³	6 +2.43 m 21.9 m³	7 +3.49 m 31.4 m³	8 +5.30 m 27.4 m³
		9 +1.28 m 7.9 m³	10 +2.02 m 18.2 m³	11 +2.70 m 24.3 m³	12 +3.90 m 20.2 m³
		13 +0.91 m 5.5 m³	14 +1.12 m 10.1 m³	15 +1.66 m 14.9 m³	16 +3.42 m 17.7 m³
		17 +0.89 m 4.2 m³	18 +1.09 m 9.8 m³	19 +2.03 m 18.3 m³	20 +4.70 m 24.3 m³
		21 +0.96 m 5.5 m³	22 +1.14 m 10.2 m³	23 +2.13 m 19.2 m³	24 +4.79 m 24.8 m³
		25 +1.03 m 7.0 m³	26 +1.17 m 10.5 m³	27 +2.17 m 19.5 m³	28 +4.78 m 24.8 m³
		29 +0.96 m 1.6 m³	30 +1.08 m 9.2 m³	31 +1.21 m 10.9 m³	32 +2.08 m 18.7 m³
		34 +1.01 m 1.3 m³	35 +1.14 m 10.3 m³	36 +1.27 m 11.4 m³	37 +2.04 m 18.3 m³
		39 +1.10 m 1.9 m³	40 +1.21 m 10.9 m³	41 +1.32 m 11.9 m³	42 +2.04 m 18.4 m³
		44 +1.20 m 5.9 m³	45 +1.33 m 12.0 m³	46 +1.43 m 12.9 m³	47 +2.01 m 18.1 m³
		49 +1.30 m 5.7 m³	50 +1.42 m 12.8 m³	51 +1.49 m 13.4 m³	52 +2.02 m 18.2 m³
		54 +1.38 m 6.8 m³	55 +1.37 m 12.4 m³	56 +1.33 m 12.0 m³	57 +1.92 m 17.3 m³
		59 +1.36 m 0.1 m³	60 +1.46 m 11.8 m³	61 +1.30 m 11.7 m³	62 +1.18 m 10.6 m³
		65 +1.48 m 1.4 m³	66 +1.60 m 14.4 m³	67 +1.47 m 13.2 m³	68 +1.35 m 12.1 m³
		71 +1.59 m 1.1 m³	72 +1.68 m 13.9 m³	73 +1.70 m 15.3 m³	74 +1.68 m 15.1 m³
		77 +1.66 m 0.2 m³	78 +1.71 m 14.4 m³	79 +1.75 m 15.7 m³	80 +2.15 m 19.3 m³
		81 +3.13 m 28.2 m³	82 +4.77 m 24.8 m³	83 +1.56 m 0.2 m³	84 +1.65 m 6.2 m³
		85 +1.74 m 15.7 m³	86 +1.96 m 17.6 m³	87 +2.87 m 25.9 m³	88 +4.27 m 38.5 m³
		89 +5.47 m 28.3 m³	90 +1.53 m 1.6 m³	91 +1.67 m 15.1 m³	92 +1.80 m 16.2 m³
		93 +2.24 m 20.2 m³	94 +3.27 m 29.4 m³	95 +4.63 m 41.7 m³	96 +5.57 m 20.6 m³
		97 +1.69 m 3.9 m³	98 +1.83 m 15.4 m³	99 +1.92 m 14.5 m³	100 +2.21 m 19.0 m³
		101 +3.06 m 27.1 m³	102 +4.53 m 25.5 m³	103 +5.54 m 1.0 m³	104 +1.85 m 0.9 m³
		105 +2.00 m 2.8 m³	106 +3.17 m 0.3 m³		